

栄団地12号線外4路線舗装修繕工事 数量総括表

1 式当り

[illegible]

舗装打換之工 数量総括表

1 式 当 り

[illegible]

計 算 書			
名 称	計 算 式	単位	数 量
舗装打換え工			
舗装版切断工 〔As舗装版 t=15cm以下〕	舗装版切断調書より $L = 118.5$	= 118.5 m	119
舗装版破碎工 〔As舗装版 t=5cm〕	車道本線 t=5cm 舗装面積計算書より $A = 2,130.8$	= 2,130.8 m ²	2,130
殻 運 搬 (アスファルト殻)	$V = 2,130.8 \times 0.05$	= 106.5 m ³	107
殻 処 理 (アスファルト殻)	殻運搬より $V = 106.5$	= 106.5 m ³	107
不 陸 整 正 工 〔補足材有り RC-40 t=3cm〕	舗装版破碎工より $A = 2,130.8$	= 2,130.8 m ²	2,130
表 層 工 〔再生密粒度As(13) t=5cm PK-3〕	車道本線 t=5cm 舗装版破碎工より $A = 2,130.8$	= 2,130.8 m ²	2,130

鋪装版切断工 箇所調書

NO. 1

[illegible]

舗 装 工 計 算 書											
測 点	点 間 距 離	舗装打換え工									
		単距離	幅	平 均	面 積	摘 要	単距離	幅	平 均	面 積	摘 要
A路線											
No. 0			5.00								
No. 1	20.00		5.00	5.00	100.0						
No. 2	20.00		5.00	5.00	100.0						
No. 3	20.00		5.00	5.00	100.0						
No. 4	20.00		5.00	5.00	100.0						
No. 5	20.00		5.00	5.00	100.0						
No. 5 + 14.20	14.20		5.00	5.00	71.0						
No. 5 + 17.50	3.30		11.70	8.35	27.6						
小 計	117.50				598.6						

舗 装 工 計 算 書											
測 点	点 間 距 離	舗装打換え工									
		単距離	幅	平 均	面 積	摘 要	単距離	幅	平 均	面 積	摘 要
B路線											
No. 0			5.00								
No. 1	20.00		5.00	5.00	100.0						
No. 1+9.40	9.40		5.00	5.00	47.0						
No. 1+13.20	3.80		13.00	9.00	34.2						
	a	b	c	S	面 積						
①	11.80	8.80	4.50	12.55	16.86						
②	8.80	4.80	5.30	9.45	10.89						
③	5.30	5.00	1.80	6.05	4.50						
小 計	33.20				213.4						

舗 装 工 計 算 書											
測 点	点 間 距 離	舗装打換え工									
		単距離	幅	平 均	面 積	摘 要	単距離	幅	平 均	面 積	摘 要
C路線											
No. 0			4. 90								
No. 1	20. 00		4. 90	4. 90	98. 0						
No. 1+6. 00	6. 00		5. 00	4. 95	29. 7						
No. 1+9. 60	3. 60		12. 70	8. 85	31. 9						
	a	b	c	S	面 積						
④	11. 70	8. 70	4. 60	12. 50	17. 33						
⑤	8. 70	4. 70	5. 00	9. 20	9. 32						
⑥	5. 00	4. 90	0. 90	5. 40	2. 20						
小 計	29. 6				188. 5						

舗 装 工 計 算 書											
測 点	点 間 距 離	舗装打換え工									
		単距離	幅	平 均	面 積	摘 要	単距離	幅	平 均	面 積	摘 要
D路線											
No. 0			4. 00								
No. 1	20. 00		4. 30	4. 15	83. 0						
No. 2	20. 00		4. 50	4. 40	88. 0						
No. 3	20. 00		4. 30	4. 40	88. 0						
No. 4	20. 00		4. 20	4. 25	85. 0						
No. 4+19. 80	19. 80		4. 20	4. 20	83. 2						
No. 5	0. 20		4. 30	4. 25	0. 9						
No. 5+2. 20	2. 20		3. 80	4. 05	8. 9						
No. 5+2. 20			4. 70	4. 25							
No. 5+11. 00	8. 80		5. 20	4. 95	43. 6						
No. 5+11. 00			5. 40	5. 30							
No. 5+12. 70	1. 70		5. 40	5. 40	9. 2						
小 計	112. 7				489. 8						

舗 装 工 計 算 書											
測 点	点 間 距 離	舗装打換え工									
		単距離	幅	平 均	面 積	摘 要	単距離	幅	平 均	面 積	摘 要
E路線											
No. 0			5.80								
No. 1	20.00		5.80	5.80	116.0						
No. 1+3.20	3.20		5.80	5.80	18.6						
No. 1+6.50	3.30		9.60	7.70	25.4						
No. 1+6.50			12.30	10.95							
No. 1+11.10	4.60		12.10	12.20	56.1						
No. 1+11.10			9.60	10.85							
No. 1+14.80	3.70		5.90	7.75	28.7						
No. 2	5.20		6.00	5.95	30.9						
No. 3	20.00		5.30	5.65	113.0						
No. 4	20.00		5.30	5.30	106.0						
No. 5	20.00		5.30	5.30	106.0						
小 計	100.0				600.7						

舗 装 工 計 算 書											
測 点	点 間 距 離	舗装打換え工									
		単距離	幅	平 均	面 積	摘 要	単距離	幅	平 均	面 積	摘 要
E路線											
	a	b	c	S	面 積						
⑦	13.00	5.20	10.80	14.50	27.36						
⑧	10.80	5.90	5.50	11.10	9.85						
⑨	5.90	5.80	0.90	6.30	2.61						
小 計					39.8						
合 計	393.0				2130.8						

1 式当り

[illegible]

区画線工 延長調書

NO. 1

名 称	測 点		数 量	摘 要
	左・右	自 至		
溶融式区画線 (実線, 巾15cm, 白)	左	NO. 0 ~ NO. 5 + 2.20	102.2	外側線(D)
	左	NO. 5 + 11.10 ~ NO. 5 + 12.70	1.6	〃
	右	NO. 0 ~ NO. 0 + 1.10	1.2	〃
	右	NO. 0 + 11.64 ~ NO. 1 + 6.54	15.2	〃
	右	NO. 1 + 15.91 ~ NO. 5 + 3.60	67.7	〃
	右	NO. 5 + 9.00 ~ NO. 5 + 12.70	5.9	〃
		合計=	193.8m	
溶融式区画線 (実線, 巾30cm, 白)	左	NO. 5 + 17.00	3.6	停止線(A)
	左	NO. 5 + 1.70	2.0	停止線(D)
	右	NO. 5 + 11.10	3.0	〃
	左	NO. 1 + 8.00 ~ NO. 1 + 11.60	3.6	停止線(E)
		合計=	12.2m	
溶融式区画線 (記号, 白)	CL	NO. 0 + 17.90	1	交差点表示(T字)A
	CL	NO. 2 + 3.30	1	〃
	CL	NO. 0 + 3.73	1	交差点表示(T字)D
	CL	NO. 1 + 9.48	1	〃
		交差点表示(T字) 計 =	4 箇所	
		巾15cm換算 5.7m/箇所×4箇所 小計=	22.8m	
	CL	NO. 5 + 5.36	1	交差点表示(十字)D
	CL	NO. 1 + 9.60	1	交差点表示(十字)E
		交差点表示(十字) 計 =	2 箇所	
		巾15cm換算 7.0m/箇所×2箇所 小計=	14.0m	
	左	NO. 5 + 6.40 ~ NO. 5 + 15.60	1	止まれ(A路線)
	左	NO. 4 + 10.17 ~ NO. 4 + 19.37	1	止まれ(D路線)
	左	NO. 4 + 12.70 ~ NO. 5 + 1.90	1	止まれ(E路線)
		止まれ 計 =	3 箇所	
		巾15cm換算 18.6m/箇所×3箇所 小計=	55.8m	
	左	NO. 1 + 9.20	1	止(E路線)
		止 計 =	1 箇所	
		巾15cm換算 5.6m/箇所×1箇所 小計=	5.6m	

延長調書

NO. 2

[illegible]