

町道富田子内部線舗装修繕工事 数量総括表

1 式当り

[illegible]

鋪 装 修 繕 工 数量總括表

1 式当り

[illegible]

計 算 書			
名 称	計 算 式	単位	数 量
路面切削工			
舗装版切断工			
As舗装版	No. 0 L=10.94m		
t=15cm以下	No. 25 L=4.46m		
	$L = 10.94 + 4.46$	= 15.4 m	15
路面切削工			
切削深 t=5cm	車道本線 t=5cm		
	舗装面積計算書より		
	$A = 2,255.2$	= 2,255.2 m ²	2,260
殻運搬			
(アスファルト切削殻)	$V = 2,255.2 \times 0.05$	= 112.8 m ³	113
殻処理			
(アスファルト切削殻)	$V = 112.8$	= 112.8 m ³	113
舗装工			
表層工			
再生密粒度	車道本線 t=5cm		
アスコン(13)	舗装面積計算書より		
t=5cm	$A = 2,255.2$	= 2,255.2 m ²	2,260

舗 装 工 計 算 書											
測 点	点 間 距 離	舗 装 工									
		単距離	幅	平 均	面 積	摘 要	単距離	幅	平 均	面 積	摘 要
No. 0			10.94								
No. 1	20.00		6.48	8.71	174.2						
No. 2	20.00		4.48	5.48	109.6						
No. 3	20.00		4.78	4.63	92.6						
No. 4	20.00		4.17	4.48	89.6						
No. 5	20.00		4.32	4.25	85.0						
No. 6	20.00		4.31	4.32	86.4						
No. 7	20.00		4.32	4.32	86.4						
No. 8	20.00		4.28	4.30	86.0						
No. 9	20.00		4.31	4.30	86.0						
No. 10	20.00		4.32	4.32	86.4						
No. 11	20.00		4.28	4.30	86.0						
No. 12	20.00		4.28	4.28	85.6						
No. 13	20.00		4.14	4.21	84.2						
No. 14	20.00		4.24	4.19	83.8						
No. 15	20.00		4.26	4.25	85.0						
No. 16	20.00		4.24	4.25	85.0						
小 計	320.00				1491.8						

舗 装 工 計 算 書											
測 点	点 間 距 離	舗 装 工									
		単距離	幅	平 均	面 積	摘 要	単距離	幅	平 均	面 積	摘 要
No. 16			4. 24								
No. 17	20. 00		4. 60	4. 42	88. 4						
No. 18	20. 00		4. 05	4. 33	86. 6						
No. 19	20. 00		3. 96	4. 01	80. 2						
No. 20	20. 00		3. 95	3. 96	79. 2						
No. 21	20. 00		4. 00	3. 98	79. 6						
No. 22	20. 00		4. 42	4. 21	84. 2						
No. 23	20. 00		4. 40	4. 41	88. 2						
No. 24	20. 00		4. 42	4. 41	88. 2						
No. 25	20. 00		4. 46	4. 44	88. 8						
小 計	180. 00				763. 4						
合 計	500. 00				2255. 2						

1式当り

[illegible]

区画線工 延長調書

NO. 1

[illegible]